

SURVEY & REMONUMENTATION

AUG 10 1998

SECTION

Filed under Remonumentation Act 345 of 1990 **LIBER 1 PAGE 246**
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

1 JUL 98 3:06 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

For corners in

Lenawee
 (County)

Located in:

Corner Code #

1. Public Land Survey	T	8-S	R	4-E	M-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec	S		T		R
	S		T		R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on April 10, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Wampler set 1/4 post Ash S 30° W 2 Beech N 84° W 5
 1891 James Blair reestablished the corner "Set stake in Drain 32 1/2 lks east of fence post
 1928 Harold Clegg surveyed Thompson Hwy. and called out "West 1/4 post Section 18, Riga (could not find) station 24+77.1 and east 1/4 line Section 13 station 25+95." Difference=117.9
 1971 I set 1" X 4' iron pipe on east bank in line with fence west and at record distance east from iron sleigh runner found at the center of Section 13
 1980 I found 1" galv. pipe on east ditch bank 10± west of west edge of pavement and recorded it in L 4 P 330.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 10, 1998 Found 1" galv. pipe on east slope of deep ditch about 2' above the water. Drove it down 12", put GER PS 13040 cap in top. I left the galv. pipe instead of replacing it with a Harrison monument as I think it is more stable than a Harrison monument because of the location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" X 4' galvanized pipe capped G.E.R. P.S. 13040 and is accepted as the best available evidence of the position of the original corner.

- Found dbl hd nail & disc in E.P. West 53.68
- Found dbl hd nail & disc in E.P. S 30° E 78.51
- End of 7" dia. concrete culvert (at widest point) N 5° W 57.09
- NW corner of house foundation S 70° E 71.40
- Carsonite post 0.5 South
- P.K. in pavement 2.3 west of pavement centerline on 1/4 line extended east 16.10
- 3/4" iron pipe @ A-6 T8S R5E South 117.83
- M-5 T8S R4E N 0° 00' 00" E 2555.32
- M-7 T8S R4E S 00° 01' 17" E 2554.19



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998

Signed by Glenn E. Richard Date 6-26-98
 Glenn E. Richard

Surveyor's Michigan License No. 13040