

SURVEY & REMONUMENTATION

OCT 19 1998

Filed under Remonumentation Act 345 of 1990

LIBER 1 PAGE 266

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

Lenawee
(County)

Located In:

Corner Code #

15 SEP 1998 8:59:11 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

- | | | | |
|------------------------------------|---------|---------|-----|
| 1. Public Land Survey | T - 8-S | R - 4-E | M-7 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on April 10, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1819 Joseph Wampler set post cor Sec. 12 & 13 Beech 6 S 18 W 22 Hickory 5 N 19 W 11
- 1891 James Blair found stake and tile
- 1928 Harold Clegg RLS 13578 found gas pipe & tile while surveying Thompson Hwy.
- 1977 I dug through the pavement and found gas pipe and bricks & replaced the gas pipe with a 1" X 4' iron pipe and I recorded it in L 4, P 43
- 1980± Lenawee Co. Road Commission rebuilt the road and set a monument box at the iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 10, 1998 Found iron pipe in monument box. I drove the re-rod in and pulled it out and it had trace of bricks or tile on it. Replaced the iron pipe with 5/8" X 3' re-rod with a Lenawee Co. Re-mon cap stamped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod in monument box with a Lenawee Co. Re-mon cap stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.

- Found "X" cut on N. end C.M.P. S 65° W 20.85
- Found "X" cut on S. end C.M.P. S 15° W 87.96
- Found "X" cut on W. end C.M.P. S 5° W 120.71
- Found "X" cut on E. end C.M.P. S 15° W 127.85
- Fd dbl hd nail & disc in E.P. S 40° E 45.67

A-7 T8S R5E South 124.74 GLO = 1.89 links = 124.74'
M-6 T8S R4E North 2554.19



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998

Signed by Glenn E. Richard Date Aug 23, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040