LIBER 1 PAGE 256

OCT 1 9 1998

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN LENAWEE COUNTY FILED

For corners in	Located In:	Corner Code #	15 SEP 1998 8:59:33 AM
Lenawee (County)	Located In.	Comer Code #	VICTORIA J. DANIELS
1. Public Land Survey	T <u>-8-S</u> R <u>- 4-E</u> T R T R	M-8	REGISTER OF DEEDS
2. Property Controlling S	T R		Register of Deeds Stamp & File Number
4. Lot No, Record 5. Private Claims	led Plat		A B C D E F G H I J K L M 1 2 3 4 9 9 10 11 12
I, Glenn E. Richard do hereby certify that under require in tines 1 and 2 above were in co- current manual of survey instruction	ements of P.A. 74, Michigan P., onformance with regulations a ns of the United States Depar	and rules therefore as required in Itment of the Interior, Bureau of I	oned 6 18 17 6 15 14 13 Land 7
Management or by a decree of a Co above were in conformance with the Court of Law; established, re- expressed below:	ne rules of the Michigan Board	l of Land Surveyors or by a Decree	e of a 9 10 30 29 28 27 26 25
NOTE: Not more than 4 cor on this certificate.	ners, all in the same tow	n and range, may be record	ied 11 12 31 32 33 34 35 36 13
A. Description of original me	onument and accessories	and/or subsequent restoration	ո:

GLO 1819 Joseph Wampler set 1/4 Sec. post Aspen 18 N 50 E 5 Sycamore 6 N 3 E 13 Couldn't find anything on this corner in any of the old survey records 1980 Dug with back hoe and found large stone. Set 1" X 3' galv. pipe on line between M-7 and M-9 T8S R4E which is on east side of the stone 0.6± east of the top of the stone. I recorded it in L 4 P 330.

1980± Lenawee County Road Commission rebuilt the road and set a monument box

Description of corner evidence found and/or method applied in restoring or reestablishing corner: B.

April 13, 1998 Found iron pipe and monument box tipped to west at west edge of the pavement. Dug out iron pipe and the monument box and reset the box and set 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 by using the previously recorded witnesses and line between M-7 and M-9 T8S R4E

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Fd. "X" on steel culvert S 85° W 15.19 Fd. "X" on steel culvert S 30° W 28.90 Fd dbl hd nail & disc in E.P. S 20° E 94.18 OF MICHIGA **JRD**

NW cor of nouse foundation 8 20° E 25.	2.01 GLEN
A-8 T8S R5E South 121.79	No. 1
	A RESTONA
	Co. Rep. Mars Prehand Date July 21, 1998
Ralified by Peer Group in accordance with P.A. 345	Co. Rep. T. Kang. Lackanff Date July 21, 1998
Signed by Buck Charles D Glenn E. Richard	Date Sept 14, 1998
Surveyor's Michigan License No. <u>13040</u>	FORM APPROVED BY MICHIGAN STATE BOARD OF LA
, -	ADAPTED FOR WO