

OCT 19 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

STATE OF MICHIGAN
LENAAWEE COUNTY
FILED

For corners in

<u>Lenawee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T-8-S R-4-E	M-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

15 SEP 1998 8:59:54 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 23, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1819 Joseph Wampler set post cor. Sec. 24 & 25 Ash 16 N 20 E Hickory 5 S 8 E 2
- 1886 James Blair found stake and stones
- 1980 I dug and found two stones, added 1" X 3' galv. pipe and recorded it in L 4 P 327
- 1980± Lenawee County Road Commission rebuilt the road and set a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 23, 1998 Found 1" X 3' galv. pipe in monument box. Replaced it with a 5/8" X 3.5' re-rod with Lenawee County re-mon cap stamped P.S. 13040. Probed and hit the stones.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3.5' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd. "X" cut on S. end C.M.P. S 30° W 38.31
- Fd. "X" cut on N. end C.M.P. N 35° W 31.34
- Cut "X" on S. end C.M.P. S 65° W 66.57
- Fd. dbl hd nail & disc in E.P. S 25° E 161.75
- NW corner of brick house S 25° E 255.35

A-9 T8S R5E South 122.86



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 21, 1998

Signed by Glenn E. Richard Date Sept. 14, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040