

SURVEY & REMONUMENTATION

OCT 19 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

SECTION

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 4-E	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

15 SEP 1998 9:01:22 AM

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 29, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1819 Joseph Fletcher set 1/4 Section post Beech 18 N 76 E 7 Beech 16 S 18 W 9
- 1891 James Blair re-established the corner (stake & tile) on a straight line and half way between M-11 and M-13.
- 1977 Walter E. Frazier and Assoc. (Kenneth Suydam PS 17636) set a 3/4" X 30" rod 39.27' north of A-12 T8S R5E on line extended north from A-12 8-5 and recorded it in L 4 P 55.
- 1980± Lenawee County Road Commission rebuilt the road and set a monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- July 13, 1998 Found 5/8" iron bar with RLS cap No. 17636 in monument box
- July 29, 1998 Replaced the 5/8" X 27" capped iron bar with a 5/8" X 3' re-rod with a Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod in a monument box with a Lenawee County Re-mon cap stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner

- dbl hd nail and re-mon tag in E.P. S 25° W 142.83
- dbl hd nail and re-mon tag in E.P. S 5° E 243.15
- NW corner of house foundation S 15° E 337.89
- Iron pipe capped G.E.R. 13040 West 29.96

A-12 T8S R5E South 39.30



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 21, 1998

Signed by Glenn E. Richard Date Aug. 23, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040