

JAN 22 2001

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee
(County)


Located In:

Corner Code #



LIBER 1

PAGE 429



- 1. Public Land Survey T - 8-S R - 4-E Corner Code # C-8
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 7, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler set 1/4 Sec. post R. Oak 18 S 76 W 8 Hickory 6 N 29 E 16
- 1878 Survey by G.E. Kedzie, County Surveyor, set a oak post at one half of the distance between the Section corners
- 1885 James Blair found stake and stones
- 1889 James Blair found 1/4 section corner
- 1907 & 1914 J.L. Richard "Found stake, stones and tile"
- 1978 I dug through the pavement, found remains of wood stake surrounded by stones, I raised to surface with 5/8" X 3' iron bar and recorded it in Liber 4, Page 99
- 1998 Found 5/8" iron bar, witnessed and drove it down below road base prior to road re-construction

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 7, 2000 Found 5/8" iron bar 20" below new asphalt pavement surrounded by stones. Placed 3/4" X 3' iron pipe over the found iron bar and 5/8" X 3' re-rod in the iron pipe and drove them all down. Capped with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box on west edge of pavement with asphalt around it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- "X" on N. end of drive C.M.P. N 45° E 48.53
- "X" on N. end of drive C.M.P. S 45° E 46.85
- Dbl. hd. nail & re-mon tag in E.P. S 40° W 20.79
- "T" post west 27.64



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 26, 2000

Signed by Glenn E. Richard Date Sept. 28, 2000
Glenn E. Richard

Surveyor's Michigan License No. 13040