

**SURVEY &
REMONUMENTATION**

AUG 10 1998

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE LIBER 1 PAGE 249

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee
(County)

Located In:

Corner Code #

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

1 JUL 98 3:06 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey		T - 8-S R - 5 - E	A-2
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling In Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on April 7, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors
1882 James Blair (County Surveyor) set a stake for the corner
1928 Harold Clegg RLS No. 13578 surveyed the road. He set a iron pipe for road center line in line with occupied line east and on south side of a 24" steel pipe
1968 I set a RR spike in the pavement in line of fence to the east and at Blair's record distance (1416') west from fence going south
1973 I found the RR spike and recorded it in Liber 2, Page 491
1980± Lenawee Co. Road Commission rebuilt the road and set a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 7, 1998 I found 1/2" X 3' re-rod in monument box 0.14 East of line between M-2 7 3 T8S R4E. I removed the 1/2" re-rod and set a 5/8" X 3' re-rod with a Lenawee County Re-mon cap stamped 13040 0.14 west on town line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod in monument box with a Lenawee Co. Re-mon cap stamped G.E.R. 13040 and this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

"X" cut on S. end of CMP N 55° W 25.51
SW corner of house foundation N 50° W 128.32
SE corner of house foundation N 35° W 100.64
SW corner of shed foundation N 85° E 112.35

M-2 T8S R4E North 44.73



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998

Signed by Glenn E. Richard Date 6-26-98
Glenn E. Richard

Surveyor's Michigan License No. 13040