

**SURVEY &  
REMONUMENTATION**

**AUG 10 1998**

Filed under Remonumentation Act 345 of 1990

**LAND CORNER RECORDATION CERTIFICATE** LIBER 1 PAGE 252

Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8 - S R - 5 - E	A-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

1 JUL 98 3:07 P.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on April 8, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	18	17	16	15	14	13							
6													
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1820 Joseph Wampler set post at intersection corner 7 & 18 Beech 20 S 71 E 9 Lynn 7 N 50 W 12
- 1889 James Blair found stake, stones and bricks. SW corner of Church N 34 1/2 E to 10 1/2 (72.93')
- 1922 Harold Clegg RLS No. 13578 "Found stake & brick. (Drove gas pipe) SW corner of Church N 37 E 72.85
- 1966 I dug and found wood stake and set a 1/2" X 4' iron pipe. SW corner of Church N 35 E 72.85 SE corner of Church N 55 E 103.60
- 1980 Lenawee County Road Commission rebuilt the road and set a monument box

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

April 8, 1998 I found the 1/2" iron pipe in the monument box and replaced it with a 5/8" X 3' re-rod with a Re-mon cap stamped P.S. 13040

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

5/8" X 3' re-rod with a Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- NW corner of Brick Church (new addition) N 20° E 93.28
- SW corner of Brick Church (new addition) N 30° E 67.30
- SE corner of Brick Church N 55° E 103.60
- Fd. P.K. in NE face of E.P. S 40° E 40.61
- NW corner of concrete hdwl S 55° W 22.76

M-5 T8S R4E North 140.56



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998

Signed by Glenn E. Richard Date 6-26-98  
Glenn E. Richard

Surveyor's Michigan License No. 13040