

SURVEY & REMONUMENTATION

AUG 10 1998

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 **LIBER 1 PAGE 253**

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

STATE OF MICHIGAN
LENAAEE COUNTY
FILED

1 JUL 98 3:07 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	T - 8-S	R - 5 - E	A-6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on April 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors
1928 Harold Clegg surveyed Thompson Hwy. and called out "West 1/4 post Section 18, Riga (could not find)
1978 I set a 3/4" X 3 1/2' iron pipe on line between the East 1/4 corner and SE corner of Section 13, T8S R4E at record jog of occupied lines given in the Thompson Hwy survey recorded it in L 4 P 111
Dbl hd nail & disc in E.P. N 35 W 131.0 Dbl hd nail & disc in E.P. N 40 E 57.10 SW corner of house foundation N 50 E 100.31

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 10, 1998 I found the iron pipe on the east ditch bank 8.5± west of the pavement and about 2' above the water. Adjusted it 0.03 E to be on line between M-6 & 7 T8S R4E. I left the iron pipe instead of replacing it with a Harrison Monument as I think it is more stable than a Harrison monument because of the location

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Iron pipe capped G.E.R. P.S. 13040 and this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner

Fd dbl nail & disc in E.P. N 35° W 130.80
Fd dbl nail & disc in E.P. N 40° E 57.14
SW corner of house foundation N 50° E 100.29
Fd iron pipe East 33.20

M-6 T8S R4E North 117.83
M-7 T8S R4E South 2436.36



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998
Signed by Glenn E. Richard Date 6-26-98
Glenn E. Richard
Surveyor's Michigan License No. 13040