

OCT 19 1998

LIBER 1 PAGE 268

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

15 SEP 1998 9:03:49 AM

For corners in

Lenawee
(County)

Located In:

Corner Code #

VICTORIA J. DANIELS
REGISTER OF DEEDS

1. Public Land Survey	T - 8-S	R - 5 - E	<u>A-10</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling In Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on August 14, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors
1888 James Blair established this corner by setting a stake and tile half way between corners he found at A-9 and A-11 8-5 which fell 1.51 3/4 chains (100.16') south of the Ogden post
1972 Tim Mohr under my direction dug through the pavement and found wood stake inside of 4" tile surrounded by bricks. Drove 3/4" X 4' iron pipe thru the wood stake. I recorded it in L 1 P 521
1980± Lenawee County Road Commission rebuilt the road and set a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 23, 1998 Found iron pipe in monument box
Aug. 14, 1998 Replaced iron pipe with 5/8" X 3' re-rod with a Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in a monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

NW corner of porch foundation S 50° E 72.13
NW corner of house foundation S 55° E 76.22
Survey mark spike with re-mon tag in 12" Cedar N 45° W 34.52
Fd dbl hd nail & disc in E.P. N 5° E 344.58
Fd dbl hd nail & disc in E.P. N 55° E 29.06

M-10 T8S R4E North 100.17



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 21, 1998

Signed by Glenn E. Richard Date Sept. 14, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040