

OCT 19 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

15 SEP 1998 9:04:09 AM

SECTION

VICTORIA J. DANIELS
REGISTER OF DEEDS

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8 - S R - 5 - E	A-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 29, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 Joseph Wampler intersect W. Bdy 119 links S of post set post cor Sec. 30 & 31 at intersection Lynn 11 N 50 W 16 Elm 23 S 27 E 18
- 1884 James Blair survey notes call for stake & bricks
- 1888 James Blair survey notes call for corner found
- 1889 James Blair survey notes call for found stake and tile
- 1972 Tim Mohr under my direction dug through the pavement and found wood stake inside of 4" tile. Drove 3/4" X 4' iron pipe thru the wood stake. I recorded it in L 1 P 521
- 1980± Lenawee County Road Commission rebuilt the road and set a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 29, 1998 Found iron pipe in monument box. Replaced it with 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- SE corner of old store building N 15° W 116.91
- SW corner of house foundation N 45° E 148.77
- NW corner of garage foundation S 45° E 138.64
- NE corner of house foundation N 85° W 90.67
- USGS B.M. S 45° E 45.57

M-11 T8S R4E North 78.54



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 21, 1998

Signed by Glenn E. Richard Date Sept. 14 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040