

**SURVEY & REMONUMENTATION**

OCT 19 1998

**SECTION**

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 270

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

15 SEP 1998 9:04:21 AM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

For corners in Lenawee (County) Located In: Corner Code #

1. Public Land Survey T-8-S R-5-E A-12  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec S T R

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 29, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors  
 1889 James Blair survey notes call for corner found. Stake, bricks & tile  
 1974 Tim Mohr under my direction dug through the pavement and found traces of brick 1' deep and soft dark spot in subsoil 2' deep. Set 3/4" X 4' iron pipe. I recorded it in L 2 P 581  
 1980± Lenawee County Road Commission rebuilt the road and set a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 13, 1998 Found iron pipe in monument box  
 July 29, 1998 Replaced iron pipe with 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in a monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

dbl. hd. nail & re-mon tag in E.P. S 35° W 108.65  
 dbl. hd. nail & re-mon tag in E.P. S 10° E 204.19  
 NW corner of house foundation S 15° E 299.72  
 iron pipe capped G.E.R. 13040 N 40° W 49.68

M-12 T8S R4E North 39.30



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 21, 1998

Signed by Glenn E. Richard Date Sept. 14, 1998  
 Glenn E. Richard

Surveyor's Michigan License No. 13040