

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Lenawee Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T - 8-S R - 5 - E C-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

LIBER 1 PAGE 362
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

15 NOV 1999 9:56:39 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 15, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	19	20	21	22	23	24							
8													
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820 Joseph Wampler Set post Sec.'s 17, 18, 19 & 20 Cottonwood 18 N 56 W 20 Ash 9 S 17 E 13
 1881 James Blair surveyed Section 20. "Found all the government corners except the East and West 1/4 posts."
 Early 1900's J.L. Richard's records called for stone
 1926 R.O.W. map for the DT&I railroad shows the corner. Doesn't described type of monumentation
 1975 Roger Meinke under my direction dug and found a large pointed stone and set a 3/4" X 4' iron pipe. I recorded it in Liber 3, Page 278
 1989 Kenneth Suydam FIP in monument box.
 1995 Steve Young found iron pipe in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 15, 1999 Found 3/4" X 4' iron pipe in monument box. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

Cut "X" on S. end CMP S 30° W 39.51
 Cut "X" on W. end CMP S 65° W 46.91
 Cut "X" on N. end CMP N 30° W 39.46
 Survey mark spike & re-mon tag in T.P. S 55° E 44.91



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999
 Signed by Glenn E. Richard Date Oct. 29, 1999
 Surveyor's Michigan License No. 13040