

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 364
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 5 - E	E-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

15 NOV 1999 9:57:34 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 5, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820 Joseph Wampler Set post corner Sec.'s 16, 17 20 & 21 Cottonwood 22 N 54 E 11 Beech 5 S 20 W 11
1881 James Blair surveyed Section 20 "Found all government corners except the East and West 1/4 posts.
1881 James Blair did survey in Section 21 and described the corner as stake and stone
1883 James Blair found the corner
Early 1900's J.L. Richard's records "Iron 13 links E. of SE corner of bridge
1925 J.L. Richard surveyed Weston Rd. His notes call out the corner but not type of monumentation
1973 Roger Meinke under direction of Werner Sommer dug and found iron under stone, smaller stones & bricks.
Set 1" X 4' iron pipe & reset stones and bricks around the iron pipe and Werner Sommer recorded it in Liber 2, Page 293
1998 I found 1" iron pipe and witnessed prior to road reconstruction

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 5, 1999 Found 1" iron pipe under base course of asphalt. Set 5/8" X 3' re-rod in top of the found iron pipe and drove both down. Set monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

Survey mark spike & re-mon tag in E.P. S 45° W 40.83
SW corner of concrete head wall N 10° W 55.17
SW corner of house foundation N 55° E 132.71
dbl. hd. nail & re-mon tag in E. P. S 80° E 228.92



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999

Signed by Glenn E. Richard Date Oct. 29, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040