

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1 PAGE 150

For corners in

Lenawee (County)

Located In:

Corner Code #

- 1. Public Land Survey T-8-S R-5-E E-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec S T R

STATE OF MICHIGAN LENAWEE COUNTY FILED

17 DEC 96 9:16 A.M.

JEANETTE D. KNOX REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (12,3) contains a black dot.

I, Glenn E. Richard, in a field survey on November 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


G.L.O. 1820, Joseph Wampler set post cor. Sec. 32 & 33, Sugar 7 South 20, Lynn 18 N 34 E 19 Couldn't find any information on this corner in any of the old survey records. June 1977, K.L. Suydam set a drag tooth and recorded it in L. 4, P. 67. November 1993, George Warnke found the drag tooth and replaced it with a 1" iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 20, 1996, Found the 1" iron pipe and replaced it with a 3/4" X 3' gas pipe and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner. Fd. dbl. hd. nail & disc in Elec. pole N 40° E 41.71 SW. corner of hse. foundation N 70° E 212.39 SE. corner of brick house S 25° W 162.65 NE. corner of brick house S 40° W 110.43 3/4" gas pipe in monument box (E-1, T9S-R5E) East 33.00



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-29-1996

Signed by Glenn E. Richard Date 12-6-96

Surveyor's Michigan License No. 13040