

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1

JAN 25 2000

PAGE 363  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

For corners in

Lenawee SECTION  
 (County)

Located in:

Corner Code #

- |                                    |         |         |     |
|------------------------------------|---------|---------|-----|
| 1. Public Land Survey              | T - 8-S | R - 5-E | F-7 |
|                                    | T       | R       |     |
|                                    | T       | R       |     |
|                                    | T       | R       |     |
| 2. Property Controlling in Section | S       | T       | R   |
|                                    | S       | T       | R   |
| 3. Miscellaneous Property in Sec   | S       | T       | R   |
|                                    | S       | T       | R   |

15 NOV 1999 9:57:20 AM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 5, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler Set 1/4 Sec. post Ash 22 S 76 W 8 Hickory 9 N 89 E 18
- 1881 James Blair found a stone
- Early 1900's J.L. Richard's records call for stake & tile on top of stone
- 1925 J.L. Richard surveyed Weston Rd. His notes show the corner but not type of monumentation
- 1973 Tim Mohr under my direction dug and found wood stake and bricks and drove 3/4" iron pipe through old rotten wood stake. I recorded it in Liber 2, Page 555
- 1977 I found iron pipe
- 1998 I found 3/4" iron pipe and witnessed prior to road reconstruction

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 5, 1999 Found 3/4" iron pipe as recorded in Liber 2, Page 555 under base course of asphalt. Set 5/8" X 3' re-rod in top of the found iron pipe and drove both down. Set monument box to allow for final course of asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Survey mark spike & re-mon tag in E.P. S 40° W 32.45
- dbl hd nail & re-mon tag in 18" Ash S 55° W 53.08
- dbl hd nail & re-mon tag in 24" Walnut S 75° W 85.86
- dbl hd nail & re-mon tag in E.P. S 75° E 272.93
- Iron pipe capped WES 12030 South 33.00
- N.E. corner of barn S 20° W 136.14



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999

Signed by Glenn E. Richard Date Oct. 29, 1999  
 Glenn E. Richard

Surveyor's Michigan License No. 13040