

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 134

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 8-S R 5-E      G-2  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
LENAAEE COUNTY  
FILED

13 NOV 96 9:06 A.M.

JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	●	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 8 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820 Joseph Wampler R. Oak 18 stands for 1/4 Section corner  
 1890 James Blair found the corner described it as stake, tile and stones  
 Early 1900 J.L. Richard record is same as Blair  
 1955± My notes and K.L. Suydam's call for "Found iron"  
 1960± Jack Gillin notes "Found axle shaft and set monument box." Was employed at Lenawee County Road Commission/  
 March 1972 I found sash weight in monument box and recorded it in Liber 1, Page 345

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 8, 1996 Found sash weight in monument box over iron pipe, bricks and stone  
 Removed the sash weight and raised the box with a 1 1/2" ring and set 3/4" X 3' gas pipe capped G.E.R. 13040 in the existing iron pipe found under the sash weight

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 SW corner of brick Parrish center N 50 W 110.30  
 NE corner of brick Parrish center N 25 W 127.17  
 corner stone of Ev. Lutheran Church N 55 E 72.67  
 found dbl. hd. nail and disc in E.P. S 60 E 49.10  
 found dbl. hd. nail and disc in E.P. S 25 E 38.07  
 found dbl. hd. nail and disc in T.P. N 50 W 19.19



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 7-16-96

Signed by Glenn E. Richard Date 10-11-96  
 Glenn E. Richard

Surveyor's Michigan License No. 13040