

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **16**

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T-8-S R-5-E	G-5
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

FILED 2:59 P.M.
 OCT 10 1994
 LENAWEE COUNTY
 JEANETTE B. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 26 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1820 Joseph Wampler set post corner Sections 9, 10, 15 & 16, Elm 10 S 11° W 19 Aspen 14 North 14 January 4, 1878 James Blair "found section corner" stake and bricks
 December 1881 James Blair "found stake"
 September 23, 1966, I found an iron pipe in the pavement which checked distance West to 1/4 corner and again in August 1977 and recorded it in L. 3, P. 543.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 7, 1993, Found iron pipe in pavement as Road Commission was scarifying the pavement and tied it off to area not under construction.
 It also checks Blairs record distance North to 1/4 corner.
 July 26, 1994, Set 3/4" iron pipe and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe, capped G.E.R. P.S. 13040, in monument box and is accepted as the best available evidence of the position of the original corner.
 "X" cut on N. end 5' C.M.P. N 45° W 24.23
 "X" cut on S. end 5' C.M.P. S 45° W 23.94
 Dbl. hd. nail and disc in Elec Pole N 45° E 44.44
 "X" cut on E. end 24" C.M.P. S 45° E 39.40
 "X" cut on W. end 24" C.M.P. S 30° W 26.62



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-15-94
 Signed by Glenn E. Richard Date Oct 10, 1994
 Surveyor's Michigan License No. 13040