

NOV 07 1994

Filed under Remonumentation Act 345 of 1990

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

LIBER 001 PAGE 17

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T - <u>8 - S</u> R - <u>5 - E</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

2:59 P.M.

OCT 10 1994

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 26 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1820 Joseph Wampler set 1/4 Sec post Ash 6" S 40° E 2 Elm 6" North 3 Survey by G.E. Kedzie, Co. Surveyor on April 6, 1877 states he found stone set by B. Kent. Records of J.L. Richard call for iron, bricks and stone. November 1971 I found stone, bricks and cast iron sleigh runner, set 3/4" iron pipe and recorded the corner in L. 2, P. 521.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 7, 1993, Found 12" spike over iron pipe which checked the remaining witnesses on the L.C.R.C. July 26, 1994, set 3/4" iron pipe over original and drove it down and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe, capped C.E.R. P.S. 13040, over 3/4" X 4' iron pipe and is accepted as the best available evidence of the position of the original corner.

SW bolt on top of well casing N 35° E 90.66
 "X" cut on face of chain link fence post N 18° E 112.15
 "X" cut on top E. end 15" C.M.P. S 60° E 41.12
 "X" cut on top S. end C.M.P. S 40° W 16.26

NE Corner of garage foundation S 53° W 184.71
 NW Corner of garage foundation S 58° W 211.30
 Dbl. hd. nail & disc in E.P. S 80° W 140.83

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-15-94
 Signed by Glenn E. Richard Date Oct 10, 1994
 Glenn E. Richard



Surveyor's Michigan License No. 13040