

SURVEY & REMONUMENTATION

SEP 08 1996

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 8-S R 5-E G-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 In Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 10 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1820 Joseph Wampler set post corner Sections 27, 28, 33 & 34 Beech 18 N 25 E 3 Beech 19 S 11 E 40
 1882, 1888, 1890 & 1891 James Blair found stake & stones
 1929 Walter Frazier called for centerline of road (iron pin) 6' east of Section corner (iron under stone)
 April 1973 Dug and found 1/4" X 1" strap iron & bricks under a stone.
 Removed stone and set 3/4" X 4' iron pipe, tile and recorded it in Liber 2, Page 339

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 10, 1996 The road is under re-construction. Found 3/4" X 2' iron pipe over 1/4" X 1" strap iron and bricks.
 Drove strap iron down with 3/4" X 3' gas pipe.
 June 26, 1996 set monument box in new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 cut "X" on S. end C.M.P. S 70 W 59.62
 cut "X" on N. end C.M.P. N 40 W 40.46
 dbl. hd. nail & disc in E.P. S 80 E 172.99
 dbl. hd. nail & Re-mon tag in E.P. S 55 W 42.77

LIBER **001** PAGE **113**

FILED

AUG 08 1996

12:57 PM

LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 7-16-96

Signed by Glenn E. Richard Date 7-29-96
 Glenn E. Richard

Surveyor's Michigan License No. 13040

