

MAY 16 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Lenawee (County)

Located In:

Corner Code #

- 1. Public Land Survey T-8-S R-5-E G-13
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec S-T-R

STATE OF MICHIGAN LENAWEE COUNTY FILED

3 DEC 96 3:18 P.M.

JEANETTE D. KNOX REGISTER OF DEEDS Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on June 10 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Cell (3,3) contains a black dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1820 Joseph Wampler set post corner Section 33 and 34 Elm 9 S 50 E 8 Sugar 10 N 11 E 16
1891 James Blair found stone.
1909 Survey by Charles Keating, Co. Surveyor, called for stone.
Early 1900's J.L. Richard records call for stone
June 1971 We dug and found wood stake surrounded by tile and stones and raised with a 3/4"X4' iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 10, 1996 Found 3/4" iron pipe in pavement which checked the two remaining witnesses.
July 8, 1996, Set 3/4" X 3' gas pipe capped G.E.R. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Dbl. hd nail and Re-mon tag in E.P. N 45° W 44.47
Dbl. hd nail and Re-mon tag in E.P. S 70° E 148.47
"X" cut on S. end C.M.P. N 10° E 145.67
G-12, T8S-R5E, North 2694.50
NE corner Section 4, T9S-R5E, East 114.67



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 7-16-96

Signed by Glenn E. Richard Date 10-11-96

Surveyor's Michigan License No. 13040