

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 354
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in Lenawee (County) Located in: Corner Code #

1. Public Land Survey T-8-S R-5-E H-3
T R
T R
T R

2. Property Controlling in Section S T R
S T R
S T R

3. Miscellaneous Property in Sec S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

15 NOV 1999 9:54:32 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 13, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler Set 1/4 Sec. post Lynn 14 N 68 W 18 Lynn 11 S 76 E 13
- 1926 Survey for D.T. & I. Railroad plans show "Found" Type of monumentation not given
- 1934 Walter Frazier found strap iron. 14" Walnut SW 56.2 NE cor. house SW 85.3
- 1960 I found strap iron
- 1975 Kenneth Suydam found iron pipe 1" below pavement and recorded it in Liber 3, Page 359 conc. cor post N 45° W 47.57
- 19? Lenawee County Road Commission record "Found strap iron, set 5/8" iron rod." I believe the monument box was set at this time.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 13, 1999 Found 3/4" X 22" re-rod in a moument box. I dug in the monument box and found 3/4" X 18" steel rod on W. side of strap iron (railroad strap rail) It leaned East. Replaced the found re-rod and steel rod and straightened the strap iron and set 3/4" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 at the location of the found 3/4" X 22" re-rod

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- NE corner of house foundation S 40° W 85.22
- dbl hd nail & re-mon tag in S. face of 28" Walnut S 60° W 57.05
- Square concrete post N 45° W 47.25
- Fd. nail & disc in NW face of E.P. S 40° E 48.70



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999

Signed by Glenn E. Richard Date Oct. 11, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040