

**SURVEY &
REMONUMENTATION**

JAN 15 1998

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 238

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 5 - E	H-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

22 DEC 97 9:26 A.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on Dec. 15, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5				15	14	13							
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler set 1/4 sec. post Ash 8 N 21 W 7 Ash 8 S 48 W 3
- 1878 James Blair "Found very old stake. Put down new stake & 2 stones"
- 1958 K.L. Suydam did survey to north. Measured 39.66 1/4 chains from SE corner Section 10 but notes don't show any monumentation at S 1/4 corner or SE corner Section 10
- 1965 +/- J. Gillin (Len. Co. Rd. Comm.) Found angle iron. 16" Maple NW 52.3
- 1969 K.L. Suydam notes show found boat spike
- 1974 I found a boat spike and I recorded it in L2, P 497
- 1993 I found a boat spike in a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 15, 1997 Found boat spike in monument box over piece of cast angle iron 18" long. The cast angle iron was between two stones. Replaced angle iron with 3/4" X 3' iron pipe capped G.E.R. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Face of 18" Maple N 45° W 52.3
- Survey marker spike & re-mon tag in 34" Ash S 75° E 88.16
- Found dbl. hd. nail & disc in E. P. N 35° E 76.46
- Found P.K. nail in E.P. S 70° W 60.90
- "X:" cut on N. end 4' CMP N 35° W 34.08
- "X" cut on S. end 4' CMP S 45° W 28.84



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97
Glenn E. Richard

Surveyor's Michigan License No. 13040