

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1991 LIBER 1 PAGE 239
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

SECTION

For corners in

Lenawee
 (County)

Located In:

Corner Code #

22 DEC 97 9:26 A.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

- | | | | |
|------------------------------------|-------|-------|-----|
| 1. Public Land Survey | T-8-S | R-5-E | H-6 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on Dec. 15, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO This position not established by original government surveyors
 1973 Jack Gillin under my direction ran lines between the monumentation at the N, S, E & W 1/4 corners and set a iron pipe at the intersection of the quarter lines and I recorded it in L2, P 497.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 15, 1997 I found the iron pipe & replaced it with a 30" Harrison monument stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Iron Pipe South 33.02
 Saw cut at N. end of CMP N 45° W 26.85
 Saw cut at S. end of CMP S 50° W 24.79
 "X" cut on N. end steel culvert S 45° E 26.74



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997
 Signed by Glenn E. Richard Date 12-17-97
 Surveyor's Michigan License No. 13040