

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1996 **LIBER 1 PAGE 235**
LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

For corners in

Lenawee
 (County)

Located In:

Corner Code #

22 DEC 97 9:25 A.M.

- | | | | |
|------------------------------------|---------|---------|-----|
| 1. Public Land Survey | T - 8-S | R - 5-E | H-7 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec | S | T | R |
| | S | T | R |

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on November 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820 Joseph Wampler set 1/4 Sec. post Cottonwood 19 S 44 W 11 Ash 10 North 8
 1883 James Blair found a stake. "Set stone & bricks on top of stake"
 1973 Jack Gillin under my direction dug and found stone, bricks and dark spot in subsoil. Set 3/4" iron pipe and I recorded it in L 2, P 497.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 26, 1997 I found 3/4" X 4' iron pipe on E. side of granite stone. Had to dig out stone to set Harrison monument. Found pieces of brick and wood stake 2' deep. Set the Harrison monument at location of found iron pipe. Split the granite stone and placed a piece of it west of the monument. Also added a brick on west & east sides of the Harrison monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison monument marked quarter corner stamped P.S. 13040 and is accepted as a careful and faithful perpetuation of the position of the original corner.

- Found dbl hd nail & disc in E.P. North 32.22
- dbl hd nail & disc in 18" pine N 30° E 79.75
- Survey mark spike & re-mon disc in 36" Ash N 80° E 158.26
- Survey mark spike & re-mon disc in E.P. S 5° E 32.89



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040