

MAY 18 1997

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 124

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 8-S R 5-E H-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

13 NOV 96 9:05 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 5 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820, Joseph Wampler set 1/4 Section post Elm 5 S 20 W 3, Elm 10 N 61 E 5
1883 James Blair "found stake"
Early 1900's J.L. Richard records "stake"
1909 Charles Keating (2" iron pipe, 2' long driven into the ground 2 1/2')
1965 I dug and found an iron pipe.
1971 I found the iron pipe and raised it with 60d spike.
1974 I found the 60d spike and recorded it in L. 2, P. 713.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 25, 1996, I found the 60d spike over short piece of 1/2" iron pipe over 2' X 24" iron pipe 12" deep and remains of wood stake.
September 5, 1996, Set 3/4" X 3' gas pipe capped G.E.R. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
NE. corner of conc. headwall N 60° W 26.75
"X" cut on east end of C.M.P. S 75° E 64.32
NW. corner of brick house S 15° W 141.17
Face of 4" well casing S 35° W 167.15
F.I.P. at H-1, T9S-R5E, East 94.07



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 8-6-1996
Signed by Glenn E. Richard Date 10-25-96
Glenn E. Richard
Surveyor's Michigan License No. 13040