

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 09

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T-8-S R-5-E	I-1
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

FILED

2:59 PM

OCT 10 1994

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on Sept. 23 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820, Joseph Wampler set post 86 links E. of post N. Ash 7 S 61W 11 Sycamore 10 S 88 E 13 October 18, 1886, James Blair states he found large stone in line with west end of bridge. M.S.H.D., March 1940, 3/4" pipe, stones and crockery. March 1958, I found a 3/4" iron pipe which checked Blair's distance from the N 1/4 corner of Section 3. August 1971, K.L. Suydam "found Iron" and recorded it L. 1, P. 265.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found iron pipe 0.15 North of south line of Section 35, T7S-R5E.

September 23, 1994, Drove found iron pipe down and set 3/4" X 3" iron pipe capped P.S. 13040 in monument box 0.15 South of found iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" iron pipe capped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- "X" cut on C.M.P. N 60° W 73.93
- "X" cut on C.M.P. S 80° W 33.27
- "X" cut on C.M.P. S 15° W 28.66
- "X" cut on C.M.P. S 45° E 44.71
- Dbl. hd. nail & disc In Elec Pole N 60° W 92.86
- SW corner Sec 35, T7S-R5E West 55.05



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-15-94
Signed by Glenn E. Richard Date Oct. 10, 1994
Glenn E. Richard
Surveyor's Michigan License No. 13040