

JAN 25 2000

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 355
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 5 - E	I-2
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

15 NOV 1999 9:54:51 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 13, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler set 1/4 Sec. post Beech 18 N 60 E 4 Sugar 10 N 84 W 35
- 1886 James Blair found railroad strap rail
- 1926 Survey for DT&I Railroad plans show "Found." Type of monumentation not given
- 1962 Kenneth Suydam dug and found 1/2" iron bar & raised to surface with railroad spike.
- 1971 Kenneth Suydam dug and found 3/4" solid iron 14" below pavement & raised with railroad spike.
- 1972 Kenneth Suydam recorded it a "Found iron pipe" but the witnesses are the same as his 1971 survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 13, 1999 Found railroad spike above 3/4" X 31" re-rod 11" deep. Found re-rod was driven on S. side of strap iron (railroad strap rail) 19" deep which was on the north side of the remains of an old wooden stake. Drove found re-rod down even with the strap iron. Set 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 on south side of strap iron. Set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in a monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

- Cut "X" in CMP N 35° W 32.21
- Cut "X" in CMP S 30° E 33.26
- Fd. dbl hd nail & aluminum disc in E. pole S 50° W 33.54
- Fd. dbl hd nail & aluminum disc in meter pole N 50° E 48.62
- 2' west of centerline Lipp hwy. & 3' South of centerline Wagner Rd.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999

Signed by Glenn E. Richard Date Oct. 29, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040