

JAN 12 5 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 356
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 5 - E	1-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

15 NOV 1999 9:55:08 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2									
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on September 13, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler set post cor. Sec's 2, 3, 10 & 11 Double Ash 18 N 78 W 8 Sycamore 9 N 84 E 19
- 1879 G.E. Kedzie Found Section corner post standing
- 1886 James Blair "Found an iron bar bricks and stone"
- 1933 Walter Frazier did a survey in Section 10. "Did not find NE cor of Sec. 10 so drove small iron "A" according to Blair's measurements. I measured from fence lines. Did not set "A" as a permanent corner but for use to line to. I think this corner could be located from Blair's survey of Section 3 but did not attempt it on this survey."
- 1967 I dug and found an iron bar
- 1975 Kenneth Suydam "found iron rod set by Consumers Power Co." about 10" below pavement, raised with 10" X 1/2" iron pipe and recorded it in Liber 3 Page 359
- 1982 I dug and found a spike over the iron bar I had found in 1967 and recorded it in Liber 5, Page 48. I also found a iron pipe in a monument box 2.80 east

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 13, 1999 I found a 1/2" X 7" iron pipe as recorded in Liber 5, Page 48 in the pavement 2.85 west of a iron pipe in a monument box as recorded in Liber 3, Page 359. I dug in the monument box and found 1/2" X 10" galv. pipe over 1/2" X 12" galv. pipe and some pieces of vitrified tile mixed in with the stone base. I dug at the 1/2" X 7" iron pipe and found 3/4" X 26" iron bar on E. side of strap iron (railroad strap rail 15" deep with wood stake on West side and yellow bricks 22" deep. I replaced the 3/4" iron bar with a 5/8" X 3' re-rod on the east side of the strap iron. I removed the existing monument box and set a 1/2" X 24" re-rod in the patched pavement 2.85 east.

Oct. 1, 1999 I set a monument box after the road was paved at the approved location 2.85 west of the previous monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

- Cut "X" on W. end CMP S 20° W 47.69
- Cut "X" on S. end CMP N 35° W 26.10
- Fd. P.K. nail & disc in E.P. N 70° E 74.03
- Added re-mon tag to found boat spike in E.P. N 70° E 74.81
- Fd. dbl hd nail and disc in wood post S 40° E 39.08
- Re-rod as recorded in Liber 3, Page 359 East 2.85
- The corner is 3' north of E.W. centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999

Signed by Glenn E. Richard Date Oct. 14, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1983