

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 236

SECTION

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - <u>8-S</u> R - <u>5-E</u>	<u>1-5</u>
	T-_____ R-_____	_____
	T-_____ R-_____	_____
	T-_____ R-_____	_____
2. Property Controlling in Section	S-_____ T-_____	_____
	S-_____ T-_____	_____
3. Miscellaneous Property in Sec	S-_____ T-_____	_____
	S-_____ T-_____	_____

22 DEC 97 9:25 A.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5					●								
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on November 25, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1820 Joseph Wampler set post cor. Sec.'s 10, 11, 14, & 15 Ash 9 S 5 E 16 Elm 18 N 48 W 30
 1876 Burton Kent "Found original corner as perpetuated by stake and stone."
 1878 James Blair "Found large stone"
 Early 1900's J.L. Richard records "Stone." Maple 10 S 43 3/4 E 57 links (37.62')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 25, 1997 The Maple called for in J.L. Richard's record is still standing. Dug hole in pavement using record bearing & distance from the maple and Burton Kent's record distance from the stone at I-6. Found a pointed stone 14" deep on top of another stone. I left the stones intact. Drilled hole 12" into the top stone. Set 1/2" X 20" hex iron bar in the hole and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" Hex iron bar capped G.E.R. 13040 in top of stone in a monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

Survey spike & re-mon tag in SW side 36" Maple S 40° E 37.83
 "X" cut on S. end C.M.P. S 45° W 24.83
 "X" cut on N. end C.M.P. N 40° W 27.91
 "X" cut on N. end C.M.P. N 35° E 35.11



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040