

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 234

SECTION

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

For corners in

Lenawee
 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------|-----------|------------|
| 1. Public Land Survey | T - 8-S | R - 5 - E | <u>1-6</u> |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec | S | T | R |
| | S | T | R |

22 DEC 97 9:25 A.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on November 20, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1820 Joseph Wampler set 1/4 Sec. post Elm 11 N 50 E 14 Ash 5 S 30 W 8
 1876 Burton Kent "Found original corner as perpetuated by stake and stone. Stumps still standing."
 Early 1900's J.L. Richard's record "stone" with two witnesses.
 1971 Roger Meinke under my direction dug and found pointed stone over large stone and set 1" X 4' iron pipe bent to be over stone. I recorded it in L 2, P 521.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 20, 1997 Found iron pipe in pavement (All 1971 witnesses are gone) Dug and found the iron pipe with top over stone set by R. Meinke in 1971. I capped the existing iron and set a monument box. The bottom of the monument box is 2" above the stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" iron pipe capped G.E.R. 13040 with top over stone in a monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

North edge of stop sign post S 50° W 46.68
 dbl. hd. nail & disc in post next to telephone pedestal S 80° E 34.65
 1/2" re-rod capped G.E.R. in top of large rock S 45° W 41.82

Iron pipe in monument box @ I-7 south 2547.93
 Iron pipe in monument box @ I-5 north 2495.42



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040