

**SURVEY &
REMONUMENTATION**

JAN 15 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 237

SECTION

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

| | | |
|---------------------------------------|-------------------------------|---------------|
| <u>Lenawee</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T - <u>8-S</u> R - <u>5-E</u> | <u>I-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

22 DEC 97 9:26 A.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Glenn E. Richard, in a field survey on November 25, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1820 Joseph Wampler set post cor. Sec.'s 14, 15, 22, & 23 Sugar 9 N 5 W 13 Beech 24
Prior to 1963, while employed by W.E. Frazier I dug and found a 4" X 4" X ? sandstone. Drove I.P. beside stone and bent top over middle of stone SW corner of stone foundation NE 122.45
1974 Found iron pipe in pavement which checked my previous witnesses and recorded it in L 3, P 17

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 25, 1997 Found iron pipe in pavement. Dug and found 3/4" X 10" iron pipe over 1/2" iron pipe. Replaced 1/2" iron pipe with 3/4" X 3' iron pipe and bent top to be vertical over the stone (about 20" deep) and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

Top stone of S.W. corner of foundation N 50° E 122.41
Survey mark spike & re-mon tag in 12" Cedar N 15° E 132.32
Survey mark spike & re-mon tag in E.P. S 45° W 42.31
Found "X" cut on N. end C.M.P. N 45° W 25.78

Iron pipe in monument box @ I-6 North 2547.93



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97
Glenn E. Richard

Surveyor's Michigan License No. 13040