

JAN 15 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1

PAGE 359  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

SECTION

For corners in Lenawee (County) Located in: Corner Code #

1. Public Land Survey	T - 8 - S	R - 5 - E	L - 3
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

15 NOV 1999 9:55:54 AM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 6, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler Set 1/4 Sec. post Ash 9 West 38 Sugar 20 S 18 E 3
- 1870 Burton Kent could not find the corner and re-established it midway between the Section corners
- 1881 James Blair found stone lying on surface of ground. Drove iron under the stone.
- 1885 James Blair surveyed sections 1 and 12 and called for drag tooth under stone
- 1971 I dug and found iron pipe in tile on end 18" deep. Raised with 3/4" X 2" iron pipe and recorded it in Liber 1, Page 9
- 1972 & 1998 I found iron pipe
- 1988 Kenneth Suydam found iron
- 1996 Mike Bartolo found 3/4" iron pipe at surface

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 6, 1999 Found 3/4" iron pipe in pavement over 3/4" X 34" iron pipe in tile on end over drag tooth. Replaced the iron pipe & drag tooth with 5/8" X 3" re-rod with Lenawee County re-mon cap stamped PS 13040 and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3" re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in a monument box and is accepted as a careful and faithful re-establishment and perpetuation of the position of the original corner.

- S.E. Cor. of concrete foundation of shed N 5 W 161.67
- FIP South 33.06
- FIP capped Mike Bartolo N 80° E 133.88
- Fd. dbl. nail & disc in E.P. South 47.90
- NW corner of concrete foundation of pump house S 40° W 32.18

M-3 T8S R5E East 2618.99  
K-3 T8S R5E West 2618.07



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999

Signed by Glenn E. Richard Date Oct. 29, 1999  
Glenn E. Richard

Surveyor's Michigan License No. 13040