

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **45**

For corners in

Lenawee
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--|------------|
| 1. Public Land Survey | T <u>8</u> - S <u>5</u> R - <u>5</u> - E | <u>M-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED
DEC 05 1994 2:01 P.M.
LENAWEE COUNTY
JEANETTE D. YNOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on November 3 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. July 1819, Joseph Fletcher set post cor. T7 & 8S - R5 & 6E, Sycamore 10 N 68 W 12, Elm 9 S 8 E 11.
November 1885, James Blair found large stone.
Early 1900's, J.L. Richard records called for large stone.
May 1970, I dug and found large stone 1.5 deep and raised with iron pipe.
September 1975, K.L. Suydam found iron pipe and recorded it in L.3, P. 306.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 3, 1994, Found 3/4" X 17" re-rod in monument box tipped. Dug down and found the stone 1.7 deep. Set 3/4" X 18" re-rod capped G.E.R., P.S. 13040 and using the two witnesses to the C.M.P., which I had taken in November 1978 before the road was re-paved.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 18" re-rod capped G.E.R., P.S. 13040 in monument box over stone and is accepted as a careful and faithful perpetuation of the position of the original corner.
"X" cut on C.M.P. N 40° W 32.83
"X" cut on C.M.P. S 45° W 31.64
Dbl. hd. nail & disc in Underground cable route marker post N 55° E 46.89
"X" cut on conc. hdwl. S 40° E 41.05



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994
Signed by Glenn E. Richard Date Nov. 11, 1994
Glenn E. Richard
Surveyor's Michigan License No. 13040