

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1

PAGE 360
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in	Located In:	Corner Code #
Lenawee (County)		
1. Public Land Survey	T - 8-S R - 5-E	M-3
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

15 NOV 1999 9:56:07 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

Glenn E. Richard, in a field survey on October 6, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO 1820 Joseph Wampler set post cor. Sec.'s 1 & 12 Ash 7 S 7 W 9 Ash 18 N 4 W 21
1870 Burton Kent found the corner from witness tree or stumps
1885 James Blair surveyed sections 1 and 12 and called for stake and bricks under stone
1970 I dug and found wood stake and stone & raised with 1" iron pipe
1978 I found 1" iron pipe in the pavement and recorded it in Liber 4, Page 194
1988 Kenneth Suydam found iron pipe in monument box.
1996 Mike Bartolo found 1 1/4" iron pipe in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Oct. 6, 1999 Found 1" X 15" iron pipe in monument box over stone probed and hit bricks under edge of stone.
Drove 5/8" X 3' re-rod on S.E. side of stone and bent top to position of the found iron pipe and capped with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.
Cut "X" on N. end CMP N 80° E 28.34
Fd. nail & disc in underground cable marker post S 30° E 64.28
Fd. dbl. hd. nail & added Lenawee County Re-mon tag in E.P. S 55° W 32.85
Fd. "X" cut on top of concrete wing wall N 40° W 27.54
L-3 T8S R5E West 2618.99



Witnessed by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999
Signed by Glenn E. Richard Date Oct. 29, 1999
Surveyor's Michigan License No. 13040