

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 369
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

15 NOV 1999 9:58:36 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - 8-S R - 5 - E	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 13, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820 Joseph Wampler Set 1/4 Sec. post Beech 10 S 20 W 14 Beech 7 N 9 W 24
1895 James Blair described the corner as Iron & Tile
1970 I dug and found a iron pipe 12" deep & raised with 1 1/4" iron pipe
1972 Werner Sommer found 1 1/4" (recorded it as 1/2") iron pipe and recorded it in Liber 1, Page 629
1999 I found 1 1/4" iron pipe in pavement that checked remaining witnesses.
Sept. 25, 1999 George Warnke found 1 1/4" iron pipe and excavated finding another iron pipe below as well as a piece of granite to the west and bricks on north and south sides. He drove iron pipe down, raised it with 1/2" X 18" re-rod and set a monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 13, 1999 Removed 1/2" X 18" re-rod from monument box and replaced it with a 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

Fd. nail & brass remonumentation shiner in 32" Sycamore N 20° E 89.40
South edge of south post of arrow sign S 85° W 14.95
Fd. nail & shiner in AT&T pole #299 N 50° E 39.78
Fd. dbl. hd. nail & shiner in AT&T pole.#300 S 45° E 46.30
Base of steel post in conc. N 35° E 31.10
1.5± West if pavement centerline

This corner was approved on 10-12-99 by the Monroe County Peer Group as a common corner for A-12 T8S R6E



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999

Signed by Glenn E. Richard Date Oct. 29, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040