

APR 01 1996

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Lenawee Located In: Corner Code #

- 1. Public Land Survey T-9-S R-1-E C-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on September 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January - February 1824, Ziba Swan, Intersect N. Bdy 3.10 chains W of post. Set post at intersection cor 5 & 6 W. Oak 10 S 23 E 21 W. Oak 36 S 44 W 60 August 18, 1966, I dug for this when I was looking for C-13-8-1, but found nothing. August 24, 1977, W.E. Frazier & Associates re-established this corner at the record jog from the corner I re-established for C-13-8-1 June 16, 1994, Found iron pipe 204.58 feet West of C-13-8-1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 13, 1995, Found iron pipe under first course of asphalt pavement, set monument box. September 25, 1995, Found iron pipe in monument box 0.02 East of the record jog from C-13-8-1 and 0.05 South of the line between B-13 and C-13, 8-1 Removed it and set 3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in the monument box at the record jog 3.10 chains (204.60) and on the line between B-13 and C-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in monument box as is accepted as the best available evidence of the position of the original corner. Dbl. hd. nail & disc in Elec. pole S 40° W 78.49 Dbl. hd. nail & disc in 20" Catalpa S 65° E 91.63 Dbl. hd. nail & disc in stub of pole N 60° E 52.98 NW corner of house S 50° E 144.91 Section corner C-13-8-1 East 204.60



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-19-95

Signed by Glenn E. Richard Date Nov 3, 1995

Surveyor's Michigan License No. 13040

FILED NOV 22 1995 LENAWEE COUNTY JEANETTE D. KNOX REGISTER OF DEEDS Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked in cell B-1.