

NOV 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 72

FILED

OCT 09 1995

LENAAWEE COUNTY JEANNETTE D. KNOX REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T-9-S R-1-E C-2
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	●	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Jan. - Feb. 1824 Ziba Swan set 1/4 sec post Hickory 12 S 53° W 35 Beech 7 N 13° E 15
 May 1929 W.E. Frazier survey of E & W 1/4 line of Sec. 6. "Found E 1/4 post, drove gas pipe."
 SW corner of house N 70° 20' E 91 links (60.06)
 June 16, 1966 I dug and found gas pipe 8" under the pavement S.W. corner of house N 70° E 60.0 and raised with iron pipe.
 August 1977 K.L. Suydam found the iron pipe and recorded it in Liber 4, Page 298.
 July 29, 1994 I dug and found the gas pipe under stone of newly constructed road and replaced it with a 3/4" X 3' gas pipe capped G.E.R. P.S. 13040

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 12, 1995 Found 3/4" gas pipe under first course of asphalt pavement and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Southwest corner of house foundation N 70° E 60.01
 Northeast corner of house foundation S 30° W 133.97
 DbI. hd. nail and disc in E.P. N 40° W 69.74
 DbI. hd. nail and disc in 18" Hickory S 25° E 81.25
 DbI. hd. nail and disc post East 26.33
 The corner is 2' West of pavement center line.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-18-95

Signed by Glenn E. Richard Date 9-28-95
 Glenn E. Richard

Surveyor's Michigan License No. 13040