

SURVEY & REMONUMENTATION

NOV 15 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 73

FILED

OCT 09 1995

LENAWEE COUNTY
JEANETTE D. F. NOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Lenawee Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T-9-S R-1-E C-3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3			●										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Glenn E. Richard, in a field survey on August 15, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January and February 1824 Ziba Swan set post corner Sec. 5, 6, 7, and 8 Beech 8 N 48° W 18
Beech 10 S 56° E 25
April 1888 Plat of Harlows Blanchard's 1st Addition to Munson surveyed by J. Blair describes corner as a stone.
June 16, 1966 I dug through the pavement and found the stone 14" deep and set 1" X 14" galvanized pipe over the stone.
November 18, 1975 I found the galvanized pipe and recorded it in Liber 3, Page 335

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 15, 1995 Found the 1" galvanized pipe in monument box which agrees with the witnesses I had in 1966 and 1975.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" X 14" galvanized pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Southwest corner of garage foundation N 60° W 82.86
Southeast corner of garage foundation N 45° W 49.30
Northwest corner of porch of old store building N 30° E 65.80
Dbl. hd. nail in post next to telephone pedestal S 60° W 50.96
Dbl. hd. nail in north post of sign S 25° E 61.86
The corner is 5' South and 2' East of the pavement center line.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-18-95

Signed by Glenn E. Richard Date 9-28-95
Glenn E. Richard

Surveyor's Michigan License No. 13040

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993