

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 337
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

1 SEP 1999 5:44:34 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u>		
(County)		
1. Public Land Survey	T - 9-S R - 2 - E	C-2
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 12, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1824 John Mullett set 1/4 Sec. post W. Oak 8 S 5 E 21 W. Oak 7 N 46 1/2 E 54 , 1873, 1882 & 1883 James Blair did surveys from this corner. Type of monumentation not given
 1935 The corner is part of the boundary of Assessor's Plat No. 1 City of Morenci
 1993 I found a iron pipe in the concrete pavement
 1994± This corner was dug out when the City of Morenci installed a storm sewer down the middle of the street.
 1998 I retraced my 1993 survey to set a P.K. nail at the location of the iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 12, 1999 The P.K. nail was gone. Dug thru asphalt pavement & found the City of Morenci had poured concrete in the sewer trench. The City employees came with air compressor and jack hammer to get thru the concrete. I set 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and a monument box
 SW corner of con. column of SW corner of porch S 45° E 78.03
 dbl hd nail & re-mon tag in E.P. West 16.60
 dbl hd nail & disc in E.P. N 30° E 34.72
 NE corner of brick porch N 45° W 68.60
 Iron pipe in concrete East 33.04



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 23, 1999
 Glenn E. Richard

Surveyor's Michigan License No. 13040