

JAN 25 2000

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 353

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 9 - S R - 2 - E	D - 1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

15 NOV 1999 9:54:11 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on November 4, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors
1876 James Blair did survey in NE 1/4 of Section 5 calls for the corner but no type of monumentation
1883 James Blair did survey for Coomer St. and calls for the corner but no type of monumentation
1975 I dug and found piece of cast iron & stone in sub soil. Set P.K. nail in the pavement 0.45 north on line between D-13 & E-13 T8S R2E and recorded it in Liber 3, Page 368
1999 Found cotton gin spike in pavement 1.09 south of location recorded in Liber 3, Page 368

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 20, 1999 Found 4" diameter cast iron pipe on end on N. side of 5" X 9" X 12" sandstone in subsoil after the pavement had been removed.
November 4, 1999 Set 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 at location approved by the Peer Group 1.09 north of the found cotton gin spike on line between D-13 and C-13 T8S R2 E. Set monument box in new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Plat monument S 75° W 119.81
Survey mark spike & Lenawee County Re-mon tag in E.P. S 65° W 62.00
M. Bartolo capped iron over plat monument South 34.07
SE corner of house foundation #9510 N 45° W 121.91
NW corner of house foundation S 35° W 154.88

D-13 T8S R2E West 25.08



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999

Signed by Glenn E. Richard Date Nov. 9, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040