

OCT 19 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

15 SEP 1998 9:04:51 AM

For corners in Lenawee (County) Located in: Corner Code #

1. Public Land Survey T-9-S R-5-E A-2
 T R
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec S T R
 S T R

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on _____ 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors
1875 Burton Kent "The west line (Section 6 T9S R5E) was run and divided prorate to establish 1/4 post
1887 James Blair found stone (Survey of Section 6 T9S R5E)
1890 James Blair found stone and bricks (Survey of Sec 1 T9S R4E)
NOTE: The distances north on Blair's 1887 and 1890 survey appear to be to a common corner but he didn't make any mention of it on the surveys
1916 Ohio-Michigan Report of State line survey "The General Land Office measurements with error prorated was adopted as the stone, corner of Sections 1 and 6
1945 Lucas County Ohio Engineer's office records call for stone
1980 Kenneth Suydam RLS 17636 found pointed stone and set 1/2" X 36" iron pipe over stone and recorded it in L4 P 318
1980± Lenawee County Road Commission rebuilt the road and set a monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 13, 1998 Found iron pipe in monument box with top bent over stone I tried to drill hole in top of stone but the top broke off. Set 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 with top over the stone. The peer group reviewed the records pertaining to this corner and M-2 T9S R5E and approved them as a common corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

dbl. hd. nail and re-mon tag in E.P. N 40° W 252.43
dbl. hd. nail and re-mon tag in E.P. S 40° W 266.30
Drill hole in top of state line post #46 S 2° W 828.98
Bolt with "X" cut on top in monument box at state line South 828.33
Steel fence post N 80° E 18.34
The corner is 5.4 East of pavement centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 21, 1998

Signed by Glenn E. Richard Date Aug 23, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040