

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 115

For corners in

Lenawee  
(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>9</u> S R <u>5</u> E | <u>E-2</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec   | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

29 OCT 96 3:12 P.M.

JEANETTE D. KNOX  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on May 22 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820 Joseph Wampler set 1/4 Section post Sugar 10 N 11 E 10 Lynn 18 S 62 W 15  
1891 James Blair "found stone set on end" Poplar 12 N 85 E 50 1/4 lks (33.17)  
1909, 1947 & 1958 Lucas Co. Ohio records "Found stone".  
Road plans on file at the Lenawee County Road Commission show the corner as being 3' east of centerline 24" Cottonwood 34.8 E

SURVEY &  
REMONUMENTATION  
MAY 16 1997  
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 22, 1996 I found a P.K. nail in the pavement. Dug and found a small R.R. spike 4" deep over a stone. Couldn't drill into stone so clipped off edge & drove 3/4" X 3' gas pipe beside stone with top over center of stone June 24, 1996, Set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 with top over stone in monument box and is accepted as the best available evidence of the position of the original corner.  
steel fence post West 27.71  
dbl hd nail & disc in E.P. 153.17 S 85 E  
fd. drill hole in top of state line post #48 S 5 W 442.81  
"X" cut on top of headwall S 50 W 30.38



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 7-16-96

Signed by Glenn E. Richard Date 10-11-96  
Glenn E. Richard

Surveyor's Michigan License No. 13040