

**SURVEY &
REMONUMENTATION**

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **130**

For corners in

Lenawee
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------------|--------------|------------|
| 1. Public Land Survey | T <u>9-S</u> | R <u>5-E</u> | <u>G-1</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec | S _____ | T _____ | R _____ |

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

13 NOV 96 9:06 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on July 25 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820, Joseph Wampler set post at intersection of corner Sec. 3 & 4, Elm 10 N 78 E 18, Ash 7 N 78 W 6 1883 James Blair "Found stone".
Early 1900's, J.L. Richard records call for stone.
1972, K.L. Suydam set 1/2" steel rod and recorded it in L. 1, P. 275

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 25, 1996, Dug and found stone 14" deep 2.0 N. & 0.2 E. of re-rod set by K.L.S. and recorded in L. 1, P. 275. Set 3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in monument box on line between G-13 and H-13, T8S-R5E, which is 114.87 East of G-13 and 2.0 South of the found stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Dbl. hd. nail & disc in NE. face of Elec. pole N 75° W 149.62
Dbl. hd. nail & Lenawee Co. re-mon tag in N. face of Elec. pole S 30° E 53.40
"X" cut on S. end C.M.P. N 30° W 168.07
G-13, T8S-R5E, West 114.87
The found stone is 2.0 North



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 8-6-1996

Signed by Glenn E. Richard Date 10-11-96
Glenn E. Richard

Surveyor's Michigan License No. 13040

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993