

SURVEY & REMONUMENTATION

Filed under Remonumentation Act 345 of 1990

SEP 03 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 114

COMMISSION

For corners in

Lenawee Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T-9-S R-5-E G-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 24 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1820 Joseph Wampler set 1/4 Section post Lynn 18 N 12 W 6 Poplar 16 N 50 E 18
1861 Lucas Co. Ohio records "Found stone"
April 1891 James Blair described corner as stone, dishes & brick
Sept. 1891 James Blair described corner as stone with "X" on top
Early 1900's J.L. Richard records call for, "stone, hard maple 24" NW 36.4
1935 Lucas Co. Ohio records "Found stone"
Nov. 1960 I found sand stone and replaced with 1" X 3' iron bar
July 1972 K.L. Suydam found the iron bar and recorded it in Liber 1, Page 273

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 24, 1996 I found 60 d spike in pave over 1" iron bar 8" deep leaning south. Dug out the iron bar and found small pieces of dishes & brick and set 3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box at record distance from "X" cuts on headwalls.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Found "X" cut on concrete hdwl S 10 E 85.99
Found "X" cut on concrete hdwl S 5 W 84.94
Found drill hole on concrete hdwl S 5 W 88.89
Found drill hole on top state line post #49 S 5° E 308.35
Found 1" iron bar in square monument box on state line south 307.54
dbl. hd. nail and Re-mon tag in 30" Maple N 10 W 135.60

FILED
AUG 08 1996 12:57 P.M.
LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	●	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 7-16-96
Signed by Glenn E. Richard Date 7-29-96
Glenn E. Richard
Surveyor's Michigan License No. 13040

