

JAN 5 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1

PAGE 373  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

SECTION

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 9 - S R - 5 - E	K-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

7 DEC 1999 1:02:53 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Glenn E. Richard, in a field survey on October 13, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler set 1/4 Sec. post R. Oak 24 N 5 E 21 Ash 9 S 78 W 9
- 1874 B. Kent County Surveyor. "Corner was identified by the witness trees
- 1901 Toledo & Western Railroad plans call for stone
- 1915 Resurvey of Michigan-Ohio State line "Stone 123.45' North of post #51"
- Lucas County Ohio Engineers Office records 1882 Bement set stone. 1947 John Liwo replaced with County monument.
- 1953 John Liwo found monument which checked record information from the south
- 1964 I found hole in top of sand stone
- 1978 I found sand stone 15" deep and raised with iron pipe and recorded it in Liber 4 Page 193
- 1991 I found iron pipe which checked the 1978 witnesses
- 1995± The Lenawee County Road Commission replaced a CMP that was 3 foot south of the corner and destroyed all evidence of the corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 13, 1999 I found the corner gone as well as all the witnesses. I retraced my 1991 survey from the NW corner and the N 1/4 and set a 30" Harrison Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument and is accepted as the best available position of the original corner.

- Survey mark spike and Lenawee County Re-mon nail in 6" Hickory West 29.68
- Dbt hd nail and re-mon tag in 10" Pine N 55° E 73.61
- Cut "X" on CMP N 80° E 36.79
- Iron pipe on Section line South 123.46
- State line monument #51 in monument box S 2° 31' 10" E 123.44

The corner is 3' north of NE-SW CMP & 5'± West of the west edge of the pavement



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 3, 1999  
Glenn E. Richard

Surveyor's Michigan License No. 13040