

**SURVEY & REMONUMENTATION**

Filed under Remonumentation Act 345 of 1990 LIBER **001** PAGE **99**

SEP 03 1996

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in

|                                    |                           |               |
|------------------------------------|---------------------------|---------------|
| <u>Lenawee</u>                     | Located In:               | Corner Code # |
| (County)                           |                           |               |
| 1. Public Land Survey              | T <u>9-S</u> R <u>5-E</u> | <u>M-1</u>    |
|                                    | T <u>8-S</u> R <u>5-E</u> | <u>M-13</u>   |
|                                    | T _____ R _____           | _____         |
|                                    | T _____ R _____           | _____         |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____         |
|                                    | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                    | S _____ T _____ R _____   | _____         |

**FILED**  
**JUN - 4 1996**  
 11:37 AM  
 LENAWEE COUNTY  
 JEANETTE D. KNOX  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Glenn E. Richard, in a field survey on October 11 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1820, Joseph Wampler set Township corner Ash 11 N 79 E 16, Cottonwood 19 S 11 E 20  
 May 1877, G.E. Kedzie described the corner as iron bar.  
 March 1895, James Blair "corner found" didn't describe the monument.  
 May 1970, I found 3/8" X 1 1/2" X ? iron bar 1.3 deep and raised with 1/2" iron pipe.  
 April 1981, I found the 1/2" iron pipe and recorded it in L.4, P. 393.  
 March 1986, K.L. Suydam used it on a survey recorded in L. 1020, P. 31  
 This corner is common to A-13, T8S-R6E and A-1, T9S-R6E  
 September 1994, George Warnke found the 1/2" iron pipe and the strap iron 1.5 deep. He placed a 1" X 36" iron pipe in a monument box and capped with Monroe Co. Remon. cap.  
 This was approved by the Monroe County peer group on October 25, 1994.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 11, 1995, Found 1" Iron pipe in monument box which checked the record witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" iron pipe in monument box capped with a Monroe Co. Remonumentation cap and is accepted as the best available evidence of the position of the original corner.  
 Found nail & disc in face of Elec. pole S 50° W 41.52  
 Found nail & disc in face of Tel. pole S 20° E 64.53  
 Found nail & disc in face of Tel. pole N 40° W 32.37  
 SW. corner of house foundation N 50° W 138.76  
 Dbl. hd. nail & disc in East face of 30" Maple N 10° W 135.15  
 Dbl. hd. nail & disc in Tel. pole N 55° E 41.06



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-18-95

Signed by Glenn E. Richard Date 1-15-96  
 Glenn E. Richard

Surveyor's Michigan License No. 13040