

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 370
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in
Lenawee
(County)

Located In: Corner Code #

- 1. Public Land Survey T-9-S R-5-E M-2
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec S T R
S T R

15 NOV 1999 9:58:51 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard in a field survey on September 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1820 Joseph Wampler set 1/4 Sec. post R. Oak 24 N 5 E 21 Ash 9 S 78 W 9
- 1895 James Blair found stake and lime stones
- 1937 Walter Frazier found old stake and stones & added iron
- 1953 Kenneth Suydam found East 1/4 corner
- 1953 Werner Sommer found iron pipe
- 1961 I found iron
- 1971 Werner Sommer found R.R. spike with cross cut on top
- 1977 I found square headed bolt with "X" on top
- 1978 I found square iron bar with "X" on top NW corner of state line post #52 S 20 E 49.09 dbl hd nail & disc in E.P. N 60 E 35.86
- 1992 I found square iron bar with "X" on top cut "X" on W. end CMP N 45 W 20.29 cut "X" on E. end CMP N 65 W 24.88
- NOTE: 1915 Survey of the Ohio-Michigan Boundary. This corner is called out as "stone, 44' North and 22' West of Post 52" quarter corner west side of Section 6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 28, 1999 Found "X" cut on top of square headed bolt 4" deep. Found piece of sand stone with drill hole in the top on S. side of granite stone 0.08 south and 0.07 west of the square headed bolt. Drilled through the sand stone at the location of the drill hole and set 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod through piece of sand stone with Lenawee County Re-mon cap stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.

- Fd. nail & disc in underground cable marker post N 55° E 35.88
- NW corner of state line post #52 S 25° E 49.02
- Hole in top of state line post #52 S 25° E 49.51
- Survey marker spike & Lenawee County Re-mon disc in 13" Ash S 50° W 36.20
- Fd. "X" cut on top of CMP N 45° W 20.30
- Fd. "X" cut on top of CMP N 60° E 24.96



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999

Signed by Glenn E. Richard Date Oct. 29, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040