

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 8. W

Luce & Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 32 and 33

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" B. Cherry (S 32 NBT) N 40° W 52 1/2 Links

6" B. Cherry (S 33 NBT) N 44° E 53 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by proportionate measure east and west along township line from corners 1/2 mile west and 1 mile east. Found old wood stake on ground near corner but could not determine where it had been standing. Note: Closing corner for Sections 4,5, T 44 N, R 8 W lies 27 links east of this corner.

Corner was placed and witnessed May 23, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler  
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 8/11/60