

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY
T 45N R 8W

DESCRIPTION OF CORNER Standard corner bet. Secs. 31-32, on South boundary of Twp.

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 9-17-68

WITNESSES TO CORNER..... 13" Cedar (S31 NBT) N10°W 9.5'



11" Soft Maple (S32 NBT) N29°E 46.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established 37 links west of the closing corner for Secs. 5-6 to south. Record indicates double corners on this portion of the twp. line.

Note: This corner marks Secs. 31-32 only.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler

DATE

4-18-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68